Speed Hump Request Summary

FAYETTEVILLE NC

START

1 Contact Person Requests Speed Hump(s)

2 City Staff Review Suitability of Road for Speed Hump

Road Is Suitable

*Road Is **NOT** Suitable*

Suitable Road
- City-Owned Residential Local Street
- Posted Speed Limit ≤ 25 mph

3 City Staff Perform Speed Study & Notify Contact Person

Road DOES NOT Meet RTMP Thresholds

Road Meets RTMP Thresholds

RTMP Thresholds
- 85% of traffic is traveling ≥ 7 mph above Posted Speed Limit
- Road experiences either…
  - ≥ 100 vehicles in one hour
  - 1,000 – 3,000 vehicles per day

4 City Staff Determine Affected Area

5 Contact Person Collects Petition Signatures

Petition Success
- 85% of households within *affected area* ④ contacted.
- 70% of households within *affected area* ④ approve.
- 100% of households adjacent to speed hump approve.

END City Does Not Install Speed Hump(s)

4 ALT Contact Person Pursues Non-Compliant Installation (Coordinate With City Staff)

END City Installs Speed Hump(s)

Rev 6/18/2024